



MELTON PARISH COUNCIL

REC(21)05.02

Tennis Court Fence

Three companies were originally approached to quote for replacing the existing tennis court chain link fencing with more robust, vandal resistant panel fencing. Funding will come from the PlayPot which is at the discretion of ESC. I have spoken to the Active Communities Officer at ESC who has indicated that the Playpot could be used for this project. Because two quotes are over the tender threshold of £25k (see Standing Order 18.c) only quote 1 could be considered. Our initial indications were that the costs would be well below £25k and so did not consider formal tendering. A fourth company was then approached for a quote.

	Quote 1	Quote 2	Quote 3	Quote 4
Cost	£19,640	£28,750	£30,520	£18,457.00
Details	<p>Remove the existing chain link fencing, angle iron posts and gate, responsibly disposing offsite.</p> <p>Supply & install approximately 191 linear metres of new 3.00m high Double Wire Mesh Panel Fencing System– 200mm x 50mm x double 6mm horizontal & single 5mm vertical wires.</p> <p>The panels will be supported on 80x40x3mm RHS Posts and 80x80x3mm SHS Corner Posts. Each post will be set in a strong concrete footing extending 0.75m into the ground to give strength and stability.</p>	<p>Secure area with Heras fencing to both ends of courts (hedge to hedge)</p> <ul style="list-style-type: none"> • Take down existing chain---link and dispose of • Break out existing fence posts and dispose of • Supply and install 3m high Twin Wire Mesh fencing with sound deadening rubber blocks to include centre panel between the ends of each court • Supply and install two single leaf gates with lintel panel over and lockable slide latch (padlocks 	<p>To take down and replace your 2 tennis court fences with 3m high system as figure 3.</p> <p>Hot dip galvanised only or galvanised and polyester powdercoated.</p> <p>The standard colour is Green RAL 6005. RAL range of colours available.</p>	<p>PREPARATION: Take down existing chainlink fencing, remove from site and dispose of.</p> <p>Supply and erect 3.0m Duo8 high double wire panel system in green to existing tennis courts perimeter with a single sided divider fence and two single gates.</p> <p>We will be responsible for any faulty materials or workmanship in conjunction with Terms and Conditions for thirty six months following completion, providing</p>

	<p>The panels will be secured with anti-tamper M8 Sheer bolts, threaded inserts and full length 40mm x 5mm pressed channel clamp bars.</p> <p>We will supply & install 2no 1.2m wide single gates infilled with the same 656 rigid wire mesh into positions chosen by the client.</p> <p>The posts are hot dip galvanised and polyester powder coated to BSEN 6497 in standard RAL Green 6005.</p>	<p>supplied by yourselves). Each gate giving access to one court.</p> <ul style="list-style-type: none"> • Finished steel work is galvanised and PPC coated green • Labour, skip & materials 		<p>the court has been properly used in accordance with instructions given to the client.</p>
--	--	--	--	--

Councillors are asked to:

Decide which of quotes 1 and 4 should be recommended to Full Council for approval and to use the PlayPot for this project on 13th January 2021.



Pip Alder
Asst Clerk and Management Officer
December 2020



Figure 1 Example of Quote 1 installation



Figure 2 Example of Quote 2 installation



Figure 3 Example of Quote 3 installation



Figure 4 Example of Quote 4 installation